WARSAW CAMPUS FINISH SCHEDULE

RM NUM	ROOM NAME	FLOOR	BASE	DOORTRIM	WALLS NORTH MATL	WALLS NORTH FINISH	WALLS EAST MATL	WALLS EAST FINISH	WALLS SOUTH MATL	WALLS SOUTH FINISH	WALLS WEST MATL	WALLS WEST FINISH	CEILING FINISH	NOTES
100	VESTIBULE	CPT-6	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-6"	
101	CORRIDOR	LIN-1, LIN-2, LIN-3, LIN-4, CPT-1, CPT-3	RB-1	PT-8	GYP.	PT-2, PT-4, IWS-1, VWC-1, VWC-2	GYP.	PT-1	GYP.	PT-1, PT-2, PT-3, PT-4, PT-5, PT-6	GYP.	PT-6, SWP-1	8'-6"-9'-6"	NOTE 3, 6
102	RECEPTION	CPT-1	RB-1	-	GYP.	PT-1	GYP.	PT-1	-	-	GYP.	PT-4	8'-6"	NOTE 3, 6
103	ADMISSIONS	CPT-2	RB-1	PT-8	GYP.	PT-1, PT-2	GYP.	PT-2	GYP.	PT-1	GYP.	PT-1	8'-6"-9'-0"	NOTE 3
104	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-2	GYP.	PT-1	GYP.	PT-1	9'-0"	
105	CORRIDOR	CPT-1, CPT-3	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-4	GYP.	PT-3	8'-6"-9'-0"	NOTE 3
106	MEN'S RESTROOM	CT-1, CT-2	CTB-1	PT-8	CBD	PT-1	CBD	PT-1	CBD	PT-1	CBD	PT-1, CT-1, CT-2	8'-6"	NOTE 2, 8
106A	JANITOR	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	8'-6"	
107	WOMEN'S RESTROOM	CT-1, CT-2	CTB-1	PT-8	CBD	PT-1	CBD	PT-1, CT-1, CT-2	CBD	PT-1	CBD	PT-1	8'-6"	NOTE 2, 8
108	CLOSET	CPT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	8'-6"	
109	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
110	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
111	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
112	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
113	OPEN OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
114	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
115	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
116	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117	OPEN OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 3
117A	HUDDLE ROOM	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117B	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117C	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117D	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117E	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117F	CLOSET	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117G	CLOSET	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117H	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117J	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117K	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
117L	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
118	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1, PT-2	GYP.	PT-1, PT-2	GYP.	PT-1	9'-0"	NOTE 3
118A	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
118B	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
118C	PURCHASING	CPT-2	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-3	9'-0"	
118D	STORAGE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
119	CASHIER	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-3	9'-0"	
120	CORRIDOR	LIN-1, LIN-2, LIN-4	RB-1	PT-8	-	-	GYP.	PT-1, PT-2	-	-	GYP.	PT-4, PT-6, SWP-1	9'-6"-10'-0"	NOTE 2, 4, 5
121	CORRIDOR	LIN-1, LIN-3, CPT-3	RB-1	PT-8	GYP.	PT-5	-	-	GYP.	PT-4, PT-2	-	-	9'-0"-9'-6"	NOTE 5
122	FACULTY LOUNGE	VCT-1, VCT-3, VCT-4,	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-3	GYP.	PT-1	9'-0"	NOTE 5
123	STUDENT LOUNGE	LIN-1, LIN-2, LIN-3, LIN-4, VCT-3	RB-1	PT-8	GYP.	PT-1	GYP.	PT-3, PT-1	GYP.	PT-3, PT-4	GYP.	PT-1	9'-6"-10'-0"	NOTE 5
124	SERVERS	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-4	GYP.	PT-1	GYP.	PT-1	9'-0"	
125	TECH	VCT-1	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
125A	OFFICE	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
126	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-2	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
127	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	

RM NUM	ROOM NAME	FLOOR	BASE	DOORTRIM	WALLS NORTH MATL	WALLS NORTH FINISH	WALLS EAST MATL	WALLS EAST FINISH	WALLS SOUTH MATL	WALLS SOUTH FINISH	WALLS WEST MATL	WALLS WEST FINISH	CEILING FINISH	NOTES
131	CORRIDOR	LIN-1, LIN-2, LIN-3, LIN-4	RB-1	PT-8	GYP.	PT-1	GYP	PT-5	GYP.	PT-5, PT-2	GYP.	PT-5	8'-6"-9'-0"	NOTE 4
132	CORRIDOR	LIN-1, LIN-3	RB-1	PT-8	-	-	GYP.	PT-3	GYP.	PT-1	GYP.	PT-6	8'-6"-9'-0"	NOTE 4
133	ELECTRIC	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	-	
134	TUTORING LAB	CPT-5	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	8'-6"-9'-0"	
135	CHILDREN'S LIBRARY	CPT-4	RB-1	PT-8	GYP.	PT-2	GYP.	PT-3	GYP.	PT-5	GYP.	PT-1	9'-0"	
137	EXISTING LIBRARY	CPT-2, EXST	RB-1	PT-8	-	-	-	-	-	-	-	-	-	NOTE 4
138	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-3	GYP.	PT-1	9'-0"	
139	STORAGE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
140	HUDDLE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	9'-0"	
141	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-3	9'-0"	
142	WORKROOM	CPT-2	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
142A	CLOSET	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
143	CORRIDOR	LIN-1, LIN-3	RB-1	PT-8	-	-	GYP.	PT-4, PT-6	GYP.	PT-1	GYP.	PT-1	9'-6"	NOTE 4, 5
144	CORRIDOR	LIN-1, LIN-2, LIN-3, LIN-4	RB-1	PT-8	GYP.	PT-2	-	-	GYP.	PT-1, PT-3	GYP.	PT-1	9'-0"-10'-0"	NOTE 1
145	MEN'S RESTROOM	CT-1, CT-2	CTB-1	PT-8	CBD	PT-1	CBD	PT-1, CT-1, CT-2	CBD	PT-1	CBD	PT-1	8'-6"	NOTE 2, 8
146	OPEN OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1, PT-2	GYP.	PT-1	9'-0"	
146A	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146B	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146C	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146D	CLOSET	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146E	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146F	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146G	CLOSET	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146H	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146J	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
146K	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
147	OPEN OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
147A	OFFICE	CPT-2	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
148	COMPUTER CLASSROOM	CPT-2, CPT-4	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-5	GYP.	PT-1, WB-1	9'-0"	NOTE 1, 7
149	COMPUTER CLASSROOM	CPT-2, CPT-5	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1, WB-1	GYP.	PT-2	GYP.	PT-1	9'-0"	NOTE 1, 7
150	GENERAL CLASSROOM	CPT-2, CPT-4	RB-1	PT-8	GYP.	PT-3	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7
151	NURSING LAB	VCT-1, VCT-2, VCT-3, VCT-4	RB-1	PT-8	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7
152	NURSING STORAGE	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
153	NURSING CLASSROOM/LAB	VCT-1, VCT-2, VCT-3, VCT-4	RB-1	PT-8	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7
154	WOMEN'S RESTROOM	CT-1, CT-2	CTB-1	PT-8	CBD	PT-1	CBD	PT-1, CT-1, CT-2	CBD	PT-1	CBD	PT-1	8'-6"	NOTE 2, 8
155	JANITOR	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
156	CORRIDOR	LIN-1, LIN-2, LIN-3, LIN-4	RB-1	PT-8	GYP.	PT-1, PT-3	GYP.	PT-6	GYP.	PT-1, PT-3	GYP.	PT-1	9'-0"-9'-6"	NOTE 1
157	CHEM/PHYSICS PREP	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
158	CHEM/PHYSICS LAB	VCT-1, VCT-3, VCT-4	RB-1	PT-8	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7
159	BIOLOGY LAB 1	VCT-1, VCT-2, VCT-3	RB-1	PT-8	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7
160	BIOLOGY PREP	VCT-1	RB-1	PT-8	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	
161	BIOLOGY LAB 2	VCT-1, VCT-2, VCT-4	RB-1	PT-8	GYP.	PT-1, WB-1	GYP.	PT-1	GYP.	PT-1	GYP.	PT-1	9'-0"	NOTE 1, 7

FINISH NOTES

1. SEE DETAIL 1/ID2.8W AND 1/ID2.9W.
2. SEE DETAIL & ELEVATION ID2.10.
3. SEE DETAIL 1/ID2.4W AND 1/ID2.5W.
4. SEE DETAIL 1/ID2.6W AND 1/ID2.7W.
5. SEE DETAIL 2/ID2.6W AND 2/ID2.7W.
6. SEE ELEVATIONS ON ID3.1.
7. SEE ELEVATION 6/ID2.10 FOR ELEVATION TYPICAL.
8. ALL GROUT ON BASE FLOORS & WALLS IN RESTROOMS ARE TO BE GT-1.

KSA
Interior Design
Post Office Box 2125
Glen Allen, VA 23058
p: 804.527.0131
f: 804.527.0623
ksainteriors.com

nbj ARCHITECTURE
A Professional Limited Company
GROVE PARK SQUARE
11537-B NUCKOLS ROAD
Richmond, Virginia 23059
(804) 273-9811 fax: (804) 273-9843

RAPPAHANNOCK COMMUNITY COLLEGE
CAMPUS RENOVATIONS
WARSAW + GLENNS, VIRGINIA
PC: 260-17712

WARSAW CAMPUS
FINISH SCHEDULE & NOTES

Date: DEC 21, 2009

REVISIONS	
NO.	DATE
2	3-3-2010

Sheet ID2.1W
File Number 09004-WARSAW-SHT-CDSET